

# Special Topic: Construction Activities



GEMS Environmental Compliance-ESDM Training Series

Tanzania • February 2017

2/24/2017" |

### SESSION OBJECTIVES:

- Understand importance of construction activities in USAID programming
  - USAID funded facilities, buildings, and infrastructure must be designed/constructed to appropriate engineering standards to minimize risk to humans and environment
- Characterize potential adverse impacts of construction activities.
- Discuss USAID approach to assessing and mitigating impacts + preparation of compliance documentation. Provide highlights from recent USAID construction survey and working group.
- Understand construction "best practices," consider evolving needs.



### USAID INFRASTRUCTURE WORK

- USAID infrastructure investments range from small-scale projects such as community water tanks to large power plants and water treatment facilities.
- USAID also makes direct infrastructure investments in schools, hospitals, health clinics, and other public buildings, as well as rural farm to market roads, trunk roads, and bridges.
- Agency's infrastructure projects are a critical component of development programs in post-conflict and post-disaster countries (but are not limited to those situations).
- Agency-wide Construction Risk Working Group (CRWG)
  piloted construction risk screening tool in six Missions
  (Ethiopia, Jordan, Nepal, Pakistan, Haiti, Jamaica)
- Construction Risk Management Mandatory Reference for ADS Chapter 201 (draft Jan. 2017)

### SMALL SCALEVS LARGE SCALE CONSTRUCTION

#### SMALL SCALE CONSTRUCTION

- USAID AFR Bureau guidance: total "disturbed area" of less than 1000m².
- Types of small-scale construction:
  - Road rehabilitation (e.g., < 10 KM rural market feeder roads)
  - Rehab of schools and health clinics (e.g., medical waste incinerators).
  - Warehouse/storage units.
  - WASH projects (e.g., boreholes, latrines).



### SMALL SCALEVS LARGE SCALE CONSTRUCTION

#### LARGE SCALE CONSTRUCTION

- New, paved roads (East Africa regional roads > 10 KM).
- Hospitals.
- Agricultural warehouses; pharmaceutical storage; cold storage.
- Large WASH municipal projects, e.g., water treatment facilities, flood protection for climate resiliency.




### DIRECT, ADVERSE ENVIRO IMPACTS OF CONSTRUCTION

- Disturbance to existing landscape/habitat; devegetation
- Sedimentation/fouling of surface waters
- Standing water
- Excess water use
- Contamination of ground and water supplies
  - Septic tank issues.
- Occupational and community health and safety hazards
- Increased air and noise pollution
- Adverse impacts of materials sourcing
- Damage to sensitive or valuable ecosystems
- Compaction of the soil and grading of the site



### ADDITIONAL IMPACTS OF CONSTRUCTION

- Use of unsustainably extracted timber
- Displacement of populations
- Worker impacts
  - Waste management issues
  - Spread of disease
- Damage to aesthetics of site/area



### ADDITIONAL IMPACTS OF CONSTRUCTION

- Potential adverse impacts on workers
- In-migration of population to take advantage of new infrastructure such as schools or health posts
- Effects on fish spawning associated with siltation of streams from soil erosion at a construction site
- The spread of disease from insect vectors breeding in flooded and abandoned quarries and borrow pits
- Inefficient/non-renewable energy use

### CONSTRUCTION PRINCIPLES/MITIGATION MEASURES

- Appropriate siting.
- Environmental compliance best practices.
  - Revegetation
- occupational health and safety compliance best practices.
- Monitor environment, health and safety performance.
  - Water quality monitoring, usage.

- Minimize greenhouse gas emissions and adapt to climate change by minimizing vulnerability through project design.
- Use of alternative/renewable energy.
- Practice environmentally and socially responsible construction contracting.



## INFRASTRUCTURE ACTIVITIES AND ENVIRONMENTAL COMPLIANCE

- Need to consider environmental compliance/impact assessment components of infrastructure activities.
- Many infrastructure activities will have a significant effect on the environment and an EA or EIS might be required.
- Smaller infrastructure activities will usually be assigned appropriate conditions (i.e., mitigation measures) within the context of an IEE.




## TYPICAL CONSTRUCTION PROGRAMMING IN TANZANIA

- Farm to market rural roads (farm to market) (>1,500 km)
- power substations and transmission lines
- small scale, e.g., repair/rehab of schools/health centers (WASH)
- agricultural storage facilities
- Irrigation projects, e.g., Dakawa:
  - upgrade of pump station, electrical work.
  - preparing boundary flood protection infrastructure, new operations building, internal access roads.
  - Rehabilitate and line main canal w concrete; upgrade secondary canals.

### COMMON CONSTRUCTION CHALLENGES

- Water availability for construction and operation.
- Not enough power.
- Volatile land use issues.
- Capacity of contractors to implement work.
- Approval for building permit from county and national governmental agencies.



### ILLUSTRATIVE CONSTRUCTION SUCCESSES

- Getting involvement from GOT and USAID.
- Green architecture (efficient energy use)
- Significant roads work underway.
- Upgraded power lines and substations.
- Irrigation projects.



# EXAMPLE EMMP FOR CONSTRUCTION PROJECT

### **Activity I: Lab Facility Construction**

IEE CONDITION	MITIGATION MEASURES	ROLES & RESPONSIBILITIES	MONITORING MEASURES AND TIMING
Limit soil erosion from excavation	Terracing and levelling the project site to reduce runoff velocity and increase infiltration of rain water into the soil.  Re-vegetate exposed areas on the site to mitigate further erosion of soil.	Project contractor	Monitor nearby water body for suspended solids at the beginning of construction and thereafter daily as construction progresses

# EXAMPLE EMMP FOR CONSTRUCTION PROJECT

### **Activity I: Lab Facility Construction**


IEE CONDITION	MITIGATION MEASURES	ROLES & RESPONSIBILITIES	MONITORING MEASURES AND TIMING
Reduce fine particle/dust discharge	Install cylcone separators in areas where fine particles/dust is generated Provide and install ventilation systems in the plant  Train operators on efficient equipment setup	Implementing partner, Project contractor	Daily observations and carry out periodic (monthly) checks during production period.
2/24/2017			15


#### USAID CONSTRUCTION SURVEY AND WORKING GROUP

\$5.6Billion

**Estimated Construction Value** 

June 1, 2011- June 30, 2013





### USAID Construction Awards (2011-2013)

Number and Estimated Value of Construction				
Large > \$50 million	23 awards	\$3 billion		
Medium \$1-10 million	271 awards	\$2 billion		
Small < \$ 1 million	318 awards	\$0.1 billion		

